






ITEMS TO ORDER/COMMENTS

-  - CLEAR ZONE GIVEN FOR NEW EXISTING MOVABLE PARTITION TRACK STEEL SUPPORT.
-  - 500kg LIGHTING/AV HANGING POINTS.
-  - EXISTING HIGH LEVEL STEEL WORK TAKEN FROM FABRISTRUT GGA DRAWING: 8910_00101-REV B
-  - EES PROPOSED NEW STEEL WORK TO SUPPORT 500KG HANGING POINTS.
-  - LIGHTING/AV UNISTRUT HANGING POINTS.

IMPORTANT INFORMATION
 SET-OUT GRID ON SITE FROM LINES 3 & C. THESE CO-ORDINATE WITH 1/4 OF EXISTING DOOR TRACK WITHIN CEILING.

FINISHES

- LAM-001 - POLYREY N-026 - CLASS '1' FIRE RATED (TO APPROVED SAMPLE)
 - LAM-002 - RESOPAL 4332EM (TO APPROVED SAMPLE)
 - MET-001 - STAINLESS STEEL - BRUSHED (SUBJECT TO SAMPLE APPROVAL)
 - PNT-001 - MATT WHITE PAINTED
 - WCV-001 - FABRITRAK
 - PSX-001 - PLEXIGLAS GS BLAU 5C18 OR SIMILAR (SUBJECT TO SAMPLE APPROVAL)
- ALL WALL PANNELLING TO BE CLASS '1' FIRE RATED

POLISHED TIMBER FINISH

VENEER

CROWN CUT HARDWOOD

QUARTER CUT

QUARTER FIGURED

OTHER

SHEEN LEVEL

5% 10% 20% OTHER

FSC PEFC OTHER

NOT CONTROLLED

DRAWING TO SITE SURVEY

DRAWING TO AGREED SIZES

SPECIFICATION COMPLETE

AB2	13/05/11	HANGING POINT POSITIONS ALTERED TO MATCH SITE SURVEY
AB1	28/03/12	HANGING POINT POSITIONS ALTERED TO SITE INSPECTION REPORT 110279A. DIMENSIONS ADDED AS REQUESTED.
REV.	DATE	

DO NOT SCALE

EE Smith IS
CONTRACTS

MORRIS ROAD, CLARENDON INDUSTRIAL ESTATE,
 LEICESTER LE2 6AL
 TELEPHONE : 0116 270 6946, FACSIMILE : 0116 270 1515
 e-mail: drawings@eesmith.co.uk

AS BUILT

PROJECT TITLE
 IBIS EARLS COURT

DRAWING TITLE
 MAIN FUNCTION ROOM
 RCP - LIGHTING/AV HANGER
 AND UNISTRUT SET-OUT

SCALE	1/50	DRAWN BY	SEB
DATE	25/05/11	CHECKED BY	NB
PROJECT No.	986	REVISION	
DRG. No.	IEC-012		AB2

1 LIGHTING/AV HANGING POINT SET-OUT PLAN
 Scale: 1:50